


COUNTY OF PLACER

BUILDING

FIRE RETARDANT ROOFING CBC 7A, CRC 327.5 & PCC 15.04

- All new construction, additions and re-roofs requires a minimum "Class A" roof covering. Re-roofing in excess of 50% of the existing structure within any one-year period shall comply with the provisions of the current regulations.
- Spaced roof sheathing is permitted when installed in accordance with CBC §1507 & Tables 23-II-D-1, 23-II-D-2, E-1 & 23-II-E-2 and CRC R803, when the design roof live load or snow load is less than 30 PSF, and spaced roof sheathing is not otherwise prohibited by the required listing of the roofing material or by the designer.
- Class A Roof Covering: Products labeled as "Class B" shakes or shingles shall be installed in accordance with an approved evaluation report which qualifies the entire assembly as meeting the Class A requirement.
- Any discrepancy in the designation of an area will need to be reviewed by the California Division of Forestry or local Fire Authority.
- The roofing installer shall further provide a completed "Certificate of Compliance" to the field inspector prior to, or at the time of the final inspection of the structure, that certifies the roof meets the "Class A" requirement and, certifies that the roofing material was installed per the manufacture's installation requirements and any applicable listing.
- If your structure is located where Pg (ground snow) is100 P.S.F. or greater, hot or cold underlayment roofing is required on all roofs from the building edge for a distance of 5 feet or to the ridge, whichever is less.
- 7. CBC Chap. 7A & CRC R327.5 The following is required:
 - a) A 36" wide No. 72 ASTM cap sheet shall be installed under all metal valleys.
 - b) Firestops between the roofing and roof deck shall be provided to prevent the intrusion of flames or embers, or cover the combustible roof decking with No. 72 ASTM cap sheet.
 - c) Screens or other means shall be provided to prevent the accumulation of leaves and other debris in the gutters.



Web Site Address: http://www.placer.ca.gov Email: building@placer.ca.gov

CLASS A FIRE RETARDANT ROOFING AND INSTALLATION CERTIFICATE OF COMPLIANCE

This is to certify that the roof covering installed on the structure identified below was installed per the manufacturer's requirements for installation, and meets the requirements for a *Class A Roof Covering* as required within all unincorporated areas of Placer County.

BUILDING PERMIT NUMBER NUMBER	ASSESSOR'S PARCEL
PROPERTY OWNER	BUILDING ADDRESS
DOOFING MANUEACTURED	DOOFING TYPE
ROOFING MANUFACTURER	ROOFING TYPE
INSTALLER (PRINT) NUMBER	CONTRACTORS LICENSE
	-
SIGNATURE (INSTALLER)	TITLE

The roofing installer shall provide this completed *Certificate of Compliance* to the field inspector prior to or at the time of the final inspection of the structure.